



- NOTES:**
1. ALL MANHOLE CONNECTIONS SHALL BE PREFABRICATED OR CORED WITH A CONCRETE CORING MACHINE.
 2. ALL MANHOLES SHALL BE VACUUM TESTED.
 3. EXTENDED BASE REQUIRED FOR ALL MANHOLES WITH MORE THAN 12-FT DEPTH OF BURY.
 4. PROVIDE A MINIMUM 0.1 FOOT IN-OUT DROP FOR STRAIGHT RUNS AND 0.2 FOOT IN-OUT DROP FOR ANGLE RUNS.
 5. PROVIDE ONLY FIRST AND LAST STEP IN MANHOLE.



STANDARD PRECAST CONCRETE MANHOLE

DETAIL No.
07000.01
SHEET 1 OF 4